

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/01/2019-20 Dated: 25-4-2019

APPROVED TENDER SCHEDULE -'B'

Item-04


Name of Work:-Improvements of Library building in yelahanka new town 5th phase chowdeshwari in chowdeshwari ward no -02.

SI	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri LOKESHA A (SRI PUSHPAGIRI ENTERPRISES)	
				Rate	Rate in Words
1	KSRB 2-1.1: Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. (Page No 6 /S.no 2.1,PWD SR 2018-19)	Cum	80.00	218.00	Rupees Two Hundred Eighteen Only
2	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no136,PWD SR 2018-19)	Cum	80.00	50.00	Rupees Fifty Only
3	KSRRB 4.1.2:- Providing and laying in position Plain Cement Concrete of mix 1:3:6 with OPC cement @ 220kgs ,with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation including cost of all materials,labour, HOM of machinery ,curing complete as per specifications. (P.13 /4.2,PWD SR 2018-19)	Cum	10.80	4543.00	Rupees Four Thousand Five Hundred Forty Three Only
4	KSRB 4-1.5:Providing and laying in position Plain Cement Concrete of mix M20 with OPC cement @ 300kgs ,with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.43cum ,with superplastisiser @ 3lts confirming to IS9 103-1999 Reaffirmed-2008,machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation,plinth and cills, including cost of all materials,labour, HOM of machinery ,curing complete as per specifications.(P13 /4.5,PWD SR 2018-19)	Cum	7.20	4660.00	Rupees Four Thousand Six Hundred Sixty Only
5	KSRB 2.6:Providing and filling of Sand in Foundation to required depth to play area for sub soil treatment including Watering ramming, with all lead and lift,etc as per specifocations. (P. No. 7 /I. No.2.13,PWD SR 2018-19)	Cum	3.60	1769.00	Rupees One Thousand Seven Hundred Sixty Nine Only

Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri LOKESHA A (SRI PUSHPAGIRI ENTERPRISES)	
			Rate	Rate in Words
6 KSRB 14.6-1: Providing and fixing of available heavy duty cobble stones 60mm thick interlock pavers, using cement and coarse sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm joints, final compaction of paver surface joints into its final level, including thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between labour and HOM of machineries complete as per specifications (P.No 103 of I.No.14.6,PWD SR 2018-19)	Sqm	72.00	921.00	Rupees Nine Hundred Twenty One Only
7 Providing and fixing precast solid concrete kerb stones made out of CC. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete(P. No. 25 I. No.5.29.2,PWD SR 2018-19)	No,s	180.00	318.00	Rupees Three Hundred Eighteen Only
8 Providing external walls with texture in approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading & unloading, all lead and lift and other incidental charges including scaffolding and removing stains, complete as per specification. (P-127/15.103,PWD SR 2018-19)	Sqm	263.33	297.00	Rupees Two Hundred Ninety Seven Only
9 Providing and Applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications (P No. 121 Item No.15.60.1 ,PWD SR 2018-19)	Sqm	482.40	85.00	Rupees Eighty Five Only
10 KSRB13-1.1 : Providing and fixing Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot) size 12.5cms x7.5cms (P-90 & 12.113.2.,PWD SR 2018-19)	Each	2.00	250.00	Rupees Two Hundred Fifty Only
11 KSRB13-1.1 :Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia.(P-90 & 12.111,PWD SR 2018-19).	Each	2.00	131.00	Rupees One Hundred Thirty One Only
12 KSRB13-1.1 :Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications..(P-92 & 13.3,PWD SR 2018-19).	Each	2.00	272.00	Rupees Two Hundred Seventy Two Only
13 KSRB 11-11.8 :Providing ,supplying & commissioning of 1 H.P submersible single phase of Make ATLANTA/SUGUNA/CRI/KIRLOSKAR/OTER EQUIVALENT PUMPS.	Unit	1.00	10206.00	Rupees Ten Thousand Two Hundred Six Only

Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri LOKESHA A (SRI PUSHAGIRI ENTERPRISES)	
			Rate	Rate in Words
14 KSRB 11-11.8 : Providing and fixing white vitreous china clay, surgeon type wash basin size 660 x 460 with a pair of 15 mm C.P. brass pillar taps with pair of elbow operated levers, C.I./M.S. brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour, curing complete as per specification. KBS 11 (Page : 83 Item No. 12.30,PWD SR 2018-19)	Unit	2.00	4028.00	Rupees Four Thousand Twenty Eight Only
15 KSRB 13-6.1-1 : Providing and fixing in position brass bib cock of approved quality 25 mm nominal bore including cost of all materials, labour and HOM of equipments with all leads, complete as per specifications. Specification No. KBS 13.2.2/13.3 (Page No.91 & Item No. 13.25,PWD SR 2018-19).	Each	2.00	206.00	Rupees Two Hundred Six Only
16 Providing and placing on terrace, polyethylene waterstorage tanks with manhole lid and suitable locking arrangements,making holes of suitable diameter for inlet, outlet and over flow pipes,including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications.(For 1000 litre capacity) (Page : 96 Item No. 13.78,PWD SR 2018-19)	Nos	2.00	5973.00	Rupees Five Thousand Nine Hundred Seventy Three Only
17 KSRB 11-15.3: Providing and fixing 453x357mm rectangular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labour complete as per specifications.(Page : 84 Item No. 12.41,PWD SR 2018-19)	Unit	2.00	934.00	Rupees Nine Hundred Thirty Four Only
18 Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit..... The pit should be filled with equal proportion of salt and charcoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc, is to be established through GI wire of size as per IS1 specification 7.3.3 of IS 732 using 12 mm dia bolts, nuts, washers and checknuts etc, the pipe shall have 16 through holes of 122 mm dia. (P.68/I.2) Electrical -SR 2015-16)	Each	1.00	2430.00	Rupees Two Thousand Four Hundred Thirty Only
19 Supplying and fixing of porcelain fuse chanel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc complete (P.32/I.3a) Electrical -SR 2015-16)	Each	6.00	44.00	Rupees Forty Four Only
20 Supply patty type fluorescent tube light fitting of 4 feet 40 watts fluorescent tube of 230 volts made of M.S. sheet and stove enameled with heavy duty polyfill aluminum choke, starter, locking type brass contact holders mounted on foldable type sheet base fully wired.for use on 230 volts AC supply including 1 Nos 4'-36/40 watts fluorecent tube A Group (P.16/I.2a) Electrical -SR 2015-16)	No	20.00	324.00	Rupees Three Hundred Twenty Four Only
21 Wiring for lighting / power circute using one of PVC insulated 1100v/grade multies and copper conductor single core cable in open or consealed system of wiring A Group materials 1.50 Sqmm materials (P.9/I.20Ib) Electrical -SR 2015-16)	Rmtr	200.00	12.00	Rupees Twelve Only

Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri LOKESHA A (SRI PUSHAGIRI ENTERPRISES)	
			Rate	Rate in Words
22 Supplying and running of GI / Copper conductor for grounding & (along with other wires of CTS or conduit system of wiring) using if necessary suitable size clamps bolts nuts and washers etc. (P.68/I.3lc) Electrical -SR 2015-16)	Rmtr	24.00	179.00	Rupees One Hundred Seventy Nine Only
23 Supplying and fixing miniature circuit breakers/isolators on existing MCB distribution boards using necessary fixing materials and wiring complete as required (P.36/I.12Ba) Electrical -SR 2015-16)	No.	8.00	300.00	Rupees Three Hundred Only
24 Supplying capacitor type ceiling fan complete with down rod blades, shakle, regulator canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system and as per technical data approved (Almanord, Unique ISI, Anchor, Crompton, Khaitan, Bajaj, Usha, Johnson make) (P.23/I.23IIa) Electrical -SR 2015-16)	Nos	8.00	1539.00	Rupees One Thousand Five Hundred Thirty Nine Only
25 Fixing a ceiling fan of all capacities and all types to the existing S hook with fan regulator to the existing board together with supplying and fixing a 5 ampers ceiling rose, necessary length of 23/0.0076 inch PVC insulated twin twisted copper wire and wiring completely. (P.29/I.8) Electrical -SR 2015-16)	Nos	8.00	85.00	Rupees Eighty Five Only
26 Supplying and fixing 32mm dia class A GI pipe bracket upto 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluorescent tube street light fitting of all capacities to GI or CI or rail or RCC pole/wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires complete. (P.28/I.12b) Electrical-SR 2015-16)	Nos	8.00	555.00	Rupees Five Hundred Fifty Five Only
27 Providing and fixing ornamental delhi benches as per design specification and fixing as per the direction of Engineer in charge of work	No,s	20.00	6885.00	Rupees Six Thousand Eight Hundred Eighty Five Only


Signature of the Contractor


Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.